BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2017-18/RD/WORK_INDENT29453

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/24/2017-18, Date: 21.02.2018

Improvements to Drains at Jai Hanuman layout Main Road (at Basavaraj Pravision Store) in Ward No. 09 (Vidyaranyapura) Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SHARATH S	
				In Figures	In Words
1	123.52	Excavation for road, drains and similar works, Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	185.95	Rupees One Hundred Eighty Five and Ninety Four Paise Only
2	428.22	Removing and refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	79.58	Rupees Seventy Nine and Fifty Eight Paise Only
3	98.82	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	657.62	Rupees Six Hundred Fifty Seven and Sixty Two Paise Only
4	488	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	870.20	Rupees Eight Hundred Seventy and Nineteen Paise Only
5	51.85	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5697.67	Rupees Five Thousand Six Hundred Ninety Seven and Sixty Seven Paise Only
6	549	Providing precast slab of 100 mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc complete as per specifications and directions of engineer in charge of the work	Sqm	1424.00	Rupees One Thousand Four Hundred Twenty Four Only
7	1355.56	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc complete as per specifications and directions of engineer in charge of the work	No	368.28	Rupees Three Hundred Sixty Eight and Twenty Eight Paise Only
8	274.5	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	27.23	Rupees Twenty Seven and Twenty Two Paise Only
9	274.5	Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	69.12	Rupees Sixty Nine and Eleven Paise Only

S. Sharath
Signature of the Contractor

19/09

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

19/09